Company Directive

STANDARD TECHNIQUE: NC7C

WPD G81 Framework Appendix Part 3 for the Installation and Record Requirements for LV Housing Developments

This document shall be read in conjunction with:

ENA Engineering Recommendation G81, Framework for Design and Planning, Materials Specification and Installation and Record for Low Voltage Housing Development Installations and Associated, New, HV/LV Distribution Substations – Part 3 Installation Records.

Author: Andy Hood

Implementation Date: October 2012

Approved by

Policy Manager

Date: 9- October 2012

All references to Western Power Distribution or WPD must be read as National Grid Electricity Distribution or NGED

NOTE: The current version of this document is stored in the NGED Corporate Information Database. Any other copy in electronic or printed format may be out of date. Copyright © 2022 National Grid Electricity Distribution

1.0 REVISION HISTORY

DATE	COMMENTS	AUTHOR
17/02/2014	Previous Revision History Table and latest Revision and Review Table have been combined.	A. Hood
04/02/2014	Removal of text relating to Adoption and Distribution System Access Agreement that has been replaced by Network Access and Adoption Agreement.	Paul B Smith
08/10/2012	1 ,	A. Hood
	Phase to neutral voltage check has been added to A1	
	Requirement to confirm cable is clear of other apparatus added to A2	
	The implementation requirements are defined in Annex B	

2.0 INTRODUCTION

- 2.1 This G81 Framework Annex specifies Western Power Distribution's requirements for the installation and record requirements for low voltage electricity underground cable networks and associated new HV/LV distribution substations for housing developments undertaken under the OFGEM Competition in Connections regime. This document shall be read in conjunction with:
 - The National Framework Documents
 - The Network Access and Adoption Agreement
 - Western Power Distribution (WPD) Housing Development Framework Appendices relating to design and materials.
 - Western Power Distribution (WPD) Housing Development Framework Appendix relating to cable recording techniques.
 - WPD Standard technique ST:SD5A, The Design of LV Domestic Connections.
 - WPD Standard technique ST:SD5C, LV Connections to Multi-occupancy Buildings.
 - WPD Standard technique ST:SD5D, Standard Arrangements for LV Cut-outs
 - WPD Standard Technique ST:SD8B Part 1, LV Underground Cable Ratings
 - WPD Standard Technique ST:SD8B Part 2, 11kV Underground Cable ratings
 - WPD Standard Technique ST:CA6, Installation of Underground Cables
 - WPD Standard Technique ST:TP21D, 11kV, 6.6kV and LV Earthing

3.0 UNDERGROUND CABLES

- 3.1 In addition to satisfying the requirements of ENA Engineering Recommendation G81 Part 3, underground cables shall be installed in accordance with ST:CA6A.
- 3.2 General installation data for WPD low voltage cables is given Table 1, below.
- 3.3 Rating information for WPD LV cables is defined in ST:SD8B Part 1 and for 11kV and 6.6kV cables in ST:SD8B Part 2.

Page revised 4 February 2014

Table 1 Cable Diameters and Minimum Bending Radii

Cable Type	Typical Overall Diameter (mm)	Minimum Bending Radius (mm)
25mm ² 1ph hybrid	12	125
35mm ² 1ph hybrid	14	125
16mm ² 1ph copper concentric	12	100
25mm ² 1ph copper concentric	14	125
16mm ² 1ph copper split concentric	15	125
25mm ² 1ph copper split concentric	18	150
25mm ² 3ph hybrid	23	200
35mm ² 3ph hybrid	25	250
16mm ² 3ph copper concentric	21	200
25mm ² 3ph copper concentric	25	200
16mm ² 3ph copper split concentric	26	250
25mm ² 3ph copper split concentric	30	250
95mm ² 3 core wavecon	35	650
185mm ² 3 core wavecon	46	850
300mm ² 3 core wavecon	55	950
95mm ² 3 core wavecon	38	650
185mm ² 3 core wavecon	53	850
300mm ² 3 core wavecon	63	950
600mm ² solidal	TBC	400
740mm ² solidal	TBC	400

4.0 PLANT

4.1 Plant shall be installed in accordance with ENA Engineering Recommendation G81 Part 3. The earthing requirements for Plant are specified in ST:TP21D.

5.0 SERVICE ENTRIES FOR NEW DWELLINGS ON RESIDENTIAL ESTATES

- 5.1 The requirements for service entries are specified in ST:SD5A. For the avoidance of doubt, service cables and ducts shall not be installed within a cavity wall as this significantly de-rates the cable.
- 5.2 Cut-out arrangements shall be in accordance with WPD Standard Technique SD5D/1

6.0 MULTI-OCCUPANCY DWELLINGS

6.1 WPD requirements, which are based on ENA Engineering Recommendation G87 are specified in ST:SD5C.

7.0 TESTS AND RECORDS

- 7.1 The details of records and tests required, together with test record sheets are given below.
- 7.2 Further WPD requirements covering underground assets recording techniques, procedures and records are detailed in WPD's Framework Document Appendix on Cable Recording Techniques.

7.3 Other data to be recorded on site

- Site location / address
- Recorded by (name and contractor) and when
- Cable sizes
- Depth of plant below final ground level
- Size, type and manufacturer of jointing chambers
- Cable drum number and manufacturer
- Cable length
- Duct and sub duct sizes. (Sections to be shown where multiple ducts are laid)
- Cable laid by and when
- Map number or reference and scale: minimum scale 1/500 for underground cable recording
- LV Link box maker, type, rating and (if present) serial number
- LV Fuse cabinet / board / pillar make, type, serial number, number of outgoing ways
- HV/LV transformer, type (eg unit), make, rating, serial number, tapping range, fixed and variable losses (from test certificate)
- HV ring main unit / tee circuit breaker make, type, ratings normal and short circuit current and serial number
- Make and type of substation housing with serial number (if present)

7.4 Test records required

Test sheets, for completion by the third party, including some aide-memoire checks are provided in Annex A of this document. These checks shall be carried out for each installation / item of equipment. It should be noted that in listing only some checks this in no way removes any of the requirements stated elsewhere.

TEST / CHECK / RECORD SHEETS

A1 Services Test/Check Sheet

SERVICES TEST / CHECK SHEET						
SITE LOCATION:						
TT /	DI	DI.	D 1 '4	T 14.	E 41 6 14	N/ / 1
House / plot	Phase (L1, L2,	Phase- neutral	Polarity	Insulation resistance	Earth fault loop	Meter box installed
number	L3)	voltage/s	and phase rotation	value	impedance	correctly,
number	LS)	(V)	(3PH)	0.5 / 1kV	value (Ω)	including
		(*)	tested and	test (MΩ)	varae (11)	gas seals?
			correct?	,		Y/N
			Y/N			

I confirm the above tests / checks and that the installation is compliant with requirements of National Framework Documents and WPD Framework Appendices

Signed
Company
Date

A2 Mains Cable Test/Check Sheet

MAINS CABLE TEST / CHECK SHEET					
SITE LOCATION:					
Item	Section 1	Section 2	Section 3		
Section / location	Section 1	Section 2	Section C		
description:					
	1				
Insulation					
resistance, ph-ph &	1				
ph-earth	1				
$0.5/1$ kV test (M Ω):	1				
Continuity checked					
and OK? (Y/N):	1				
	1				
Trench depth	1				
checked and OK	1				
(Y/N):	1				
Cable clear of other					
utility apparatus?	1				
(Y/N):	1				
Cobla markar tana					
Cable marker tape laid throughout	1				
length? Y/N	1				
rengur: 1/1V	1				
Reinstatement					
compliant with	1				
NRSWA spec.,	1				
where applicable?	1				
(Y/N):					
I confirm the above	re tests / checks a	nd that the installation	on is compliant with		
I confirm the above tests / checks and that the installation is compliant with requirements of National Framework Documents and WPD Framework Appendices					
•			1.1		
C:1					
Signed					
Company					
Date					

A3 PME Electrode Test/Record Sheet

PME ELECTRODE TEST / RECORD SHEET				
SITE LOCATION –				
Describe location of electrode	Earth resistance value - Ohms			
2 0001100 100001011 01 010001000	Switch residential transfer of the same of			
I confirm the above tests / checks and that t requirements of National Framework Documents an				
Signed				
Company				
Date				

A4 Substation Test/ Check Sheet

SITE LOCATION –	
Test / check	Result
Earthing:	
Value of HV earth resistance or combined HV/LV earth resistance, as	
applicable (Ohms):	
Value of LV earth resistance (Ohms)	
(Only applicable where HV and LV earths are segregated)	
Overlap resistance (Ohms)	
(Only applicable where HV and LV earths are segregated)	
HV earth link position? (In / Out)	
LV Fuse Cabinet:	
Insulation resistance 500/1000V (M Ω)	
All fuse-way carriers in place? Y/N	
LV Protection - Ratings of fuses installed (A), by fuse-way or circuit	
breaker settings, as applicable.	
LV Generator Connectors Provided (Y/N)	
HV/LV Transformer:	
Insulation resistances HV-LV winding / earth 5kV HV (GΩ)	
Pressure test, value (kV) and duration (minutes)	
Voltage and phasing checks OK? (Y/N)	
Tap position (1,2 etc.) and % setting (+/- %)	
Oil moisture content ppm	
Oil electric breakdown strength kV / gap	
Confirmation from oil supplier that PCB content <5ppm Y/N	-
HV Switchgear / HV Protection:	
Switchgear insulation resistance 5kV test ($G\Omega$)	
Switchgear pressure test value (kV) and duration (minutes)	
Protection test, secondary injection or dummy HV fuse tester (e.g. B&S	
device) OK? (Y/N)	
HV Protection Setting (fuse rating (A), CT ratio, relay type and setting/s	
etc.) as applicable.	
Functional test of interlocks and operation OK? (Y/N)	
Insulation test of any loose test devices (test plugs etc.) $(G\Omega)$	
Gas pressure indication satisfactory? (Y/N)	
Busbar resistance if work includes connections of busbars, new to new	
or new to existing. (Micro Ohms, i.e. $\mu\Omega$)	

Busbar resistance if work includes connections of busbars, new to new or new to existing. (Micro Ohms, i.e. $\mu\Omega$)	,
I confirm the above tests / checks and that the installation is compliant v	vith requirements of
National Framework Documents and WPD Framework Appendices	
Signed	
Date	

A5 HV Cable Test/Check Sheet

HV CABLE TEST / CHECK SHEET					
SITE LOCATION:					
Item	Section 1	Section 2	Section 3		
Section / location description:					
Insulation resistance, ph-ph & ph-earth 0.5 /1kV test (MΩ):					
Continuity checked and OK? (Y/N):					
Trench depth checked and OK (Y/N):					
Cable clear of other utility apparatus? (Y/N):					
Cable marker tape laid throughout length? Y/N					
Reinstatement compliant with NRSWA spec., where applicable? (Y/N):					
NOTE – Following HV "closing" jointing by WPD to connect into WPD network, WPD undertake insulation and pressure tests of the circuit prior to energisation.					
I confirm the above tests / checks and that the installation is compliant with requirements of National Framework Documents and WPD Framework Appendices					
Signed					
Company					
Date					

A6 HV Polymeric VLF Test Sheet

TE LOCATION-			
Test Voltage	Test Points	Time	Result
2.5 Uo	All Phases to Earth	30 min	
2.5 Uo	Phase 1 to Phase 2	30 min	
2.5 Uo	Phase 1 to Phase 3	30 min	
	Phase 2 to Phase 3	30 min	

Note:- Where the cable is to be connected to an existing Western Power Distribution cable, the above test shall be carried out by an authorised member of Western Power Distribution.

I confirm the above tests/checks and that the installation is compliant with requirements of National Framework Documents and WPD Framework Appendices

Signed	
Company	
Date	

A7 AC Switchgear Pressure Test Sheet

AC PRESSURE TEST FOR 11 kV SWITCHGEAR (NOT CONNECTED)					
SITE LOCATION-					
Manufacturer:					
Type:					
Serial Number:					
Switch 1					
Test Voltage	Test Points	Time	Result		
24kV	All Phases to Earth	1 min			
24kV	Phase 1 to Phase 2	1 min			
24kV	Phase 1 to Phase 3	1 min			
24kV	Phase 2 to Phase 3	1 min			
24kV	All Phases Across	1 min			
	open switch				
Switch 2					
Test Voltage	Test Points	Time	Result		
24kV	All Phases to Earth	1 min			
24kV	Phase 1 to Phase 2	1 min			
24kV	Phase 1 to Phase 3	1 min			
24kV	Phase 2 to Phase 3	1 min			
24kV	All Phases Across	1 min			
	open switch				
Switch 3					
Test Voltage	Test Points	Time	Result		
24kV	All Phases to Earth	1 min			
24kV	Phase 1 to Phase 2	1 min			
24kV	Phase 2 to Phase 3	1 min			
24kV	Phase 1 to Phase 3	1 min			
24kV	All Phases Across	1 min			
	open switch				

Note:- These tests must be carried out prior to any cable being connected to the switch.

Where the switch is mounted directly on to a transformer the 11kV windings of the transformer shall disconnected from the switch prior to the test commencing.

I confirm the above tests/checks and that the installation is compliant with requirements of National Framework Documents and WPD Framework Appendices

igned
Company
Date

A8 Transformer Test Sheet

11kV/415V TRANS	SFORMER TESTS			
SITE LOCATION-				
Manufacture				
Size KVA				
Serial Number				
Tap Setting				
HV WINDING DC PRESSURE TEST				
Test Voltage	Test Points	Time	Result	
18kV	Winding to Earth	15 min		
LV WINDINGS				
1000V	Winding to Earth	1 min		

I confirm the above tests/checks and that the installation is compliant with requirements of National Framework Documents and WPD Framework Appendices

Signed	
Company	
Date	

SUPERSEDED DOCUMENTATION

This document supersedes WPD Appendix G81-3.1 Issue G and with WPD Appendix G81-3.2 Issue D 3 months from the issue of this document. See also Appendix E.

APPENDX C

ASSOCIATED DOCUMENTATION

ENA ER G81 Part 1

ENA ER G81 Part 2

ENA ER G81 Part 3

ENA ER G81 Part 4

ENA ER G81 Part 5

ENA ER G81 Part 6

ENIA ED COLD 45

ENA ER G81 Part 7

Western Power Distribution (WPD) Housing Development Framework Appendices relating to design and materials.

Western Power Distribution (WPD) Housing Development Framework Appendix relating to cable recording techniques.

WPD Standard technique ST:SD5A, The Design of LV Domestic Connections.

WPD Standard technique ST:SD5C, LV Connections to Multi-occupancy Buildings.

WPD Standard technique ST:SD5D, Standard Arrangements for LV Cut-outs

WPD Standard Technique ST:SD8B Part 1, LV Underground Cable Ratings

WPD Standard Technique ST:SD8B Part 2, 11kV Underground Cable ratings

WPD Standard Technique ST:CA6, Installation of Underground Cables

WPD Standard Technique ST:TP21D, 11kV, 6.6kV and LV Earthing

APPENDIX D

POLICY IMPACT

This document is applicable to all ICPs involved in the design, installation and recording of LV domestic connections. This document combines the existing requirements of WPD Appendix G83-3.1 Issue G and WPD Appendix G83-3.2 Issue D. The installation requirements for flats are now included in ST:SD5C.

APPENDIX E

IMPLEMENTATION

For a period of 3 calendar months from the date of issue of this document ICPs may either comply with WPD Appendix G81-3.1 Issue G and WPD Appendix G81-3.2 Issue D or alternatively comply with the requirements of this document. After this 3 month period this document shall be implemented in full.

APPENDIX F

KEY WORDS

G81, Competition in Connections, Housing, Framework, Independent Connection Provider, ICP, Appendix, Installation, Record, Records, Recording.